

Kellie Martinec

From: Lisa Lucero <llucero@txoga.org>
Sent: Monday, April 01, 2013 12:07 PM
To: rulescoordinator
Cc: Mari Ruckel; ctredway@austin.rr.com; Leslie Savage
Subject: TXOGA Comment Submission to Railroad Commission of Texas RE: Proposed Amendments to 16 TAC, Chapter 3
Attachments: TXOGA comments to RRC 4.1.2013.pdf; TxOGA Revisions SWR 13 (4.1.13).pdf


Re: Proposed Amendments 16 TAC, Chapter 3
§3.13, relating to Casing, Cementing, Drilling, and Completion Requirements
§3.99, relating to Cathodic Protection Wells
§3.100, relating to Seismic Holes and Core Holes

Attn: Rules Coordinator, Railroad Commission of Texas

Attached please find comments provided by the Texas Oil and Gas Association on the Proposed Amendments to 16 TAC, Chapter 3, listed above.

Should you have additional questions or comments, please contact Mari Ruckel, Vice President, Government and Regulatory Affairs, Texas Oil and Gas Association at mruckel@txoga.org.

Thank you,
Lisa Lucero
Texas Oil & Gas Association
304 West 13th Street
Austin, Texas 78701
512.478.6631 Office
llucero@txoga.org



TEXAS OIL & GAS ASSOCIATION

Janey Jones, Austin
Executive Director

Robert L. Jooney, Austin
President

Delbert M. Bowling, Austin
Secretary and Treasurer

William L. Farris, Austin
Assistant Secretary and Treasurer
and Director of Compliance

Cory A. Pomeroy, Austin
Vice President and General Counsel

Max V. Backel, Austin
Vice President for Government &
Regulatory Affairs

Ira Sauer, Austin
Executive and Vice President for Energy

April 1, 2013

Rules Coordinator
Office of General Counsel
Railroad Commission of Texas
P.O. Box 12967
Austin, Texas 78711

Submitted to: rulescoordinator@rrc.state.tx.us

Re: Proposed Amendments 16 TAC, Chapter 3
§3.13, relating to Casing, Cementing, Drilling, and Completion Requirements
§3.99, relating to Cathodic Protection Wells
§3.100, relating to Seismic Holes and Core Holes

District Vice-Presidents

Harold D. Courson, Amarillo
District Vice President

Lance R. Byrd, Dallas
District Vice President

Dan Allen Hughes, Jr., Beeville
District Vice President

Allan D. Frizzell, Abilene
District Vice President

David W. Killam, Laredo
District Vice President

Curtis W. Mewbourne, Tyler
District Vice President

Alan L. Smith, Houston
District Vice President

Douglas C. Robison, Midland
District Vice President

W. M. Thacker, Jr., Wichita Falls
District Vice President

Dear Coordinator:

TXOGA is the largest and oldest petroleum organization in Texas, representing more than 5,000 members. The membership of TXOGA produces in excess of 90 percent of Texas' crude oil and natural gas, operates 100 percent of the state's refining capacity, and is responsible for the vast majority of the state's pipelines. According to the most recent data, the oil and gas industry employs 352,000 Texans, providing payroll and benefits of over \$41 billion in Texas alone. In addition, large associated capital investments by the oil and gas industry generate significant secondary economic benefits for Texas. TXOGA member companies produce a quarter of the nation's oil, a third of its natural gas and account for one-fourth of the U.S. refining capacity.

Our members support the efforts of the Commission to clarify and strengthen the minimum requirements for well construction in Texas. During stakeholder meetings and in written comments submitted in November, TxOGA suggested revisions to the initial Railroad Commission (RRC) staff proposal and we greatly appreciate the response to our recommendations.

Our member companies have a few remaining concerns that are outlined below and the attached revisions that includes explanations relation to each explanation.

- **3.13(a)(2)(N) Relating to the definition of "Overpressured Zone"**

TxOGA recommended replacing the term "overpressured zone" with "potential flow zone" throughout the rule because the definition of "overpressured zone" was inconsistent with industry nomenclature and understanding.

RRC staff did not change the terminology but instead revised the definition. TxOGA disagrees with the revised language as it infers that normal pressure is a hazard and we still believe that "potential flow zone" is more appropriate terminology.

- **3.13(a)(4)(B) Relating to cementing standards.**

RRC staff did incorporate most of TxOGA suggestions under this section, however, language was excluded allowing for the use of API Cement/Fly Ash blends or ASTM Cement/Fly Ash blends. These blends are used on virtually every well in the state.

- **3.13(a)(6)(B)(iii) Relating to ram type blowout prevention equipment.**

Requirements under this section will make the use of expensive variable-type rams a necessity in the Permian Basin.


- **3.13(a)(7)(A) Relating to minimum yield pressure rating for casing that will be subjected to hydraulic fracturing.**

The RRC staff proposal requires that all casing installed in a well be subjected to hydraulic fracturing have a minimum yield pressure rating of at least 1.15 times the maximum pressure to which the casing will be subjected. The industry standard is 1.10 and adjusting to this increase would be a significant cost to most operators.

Again, our members are supportive of this effort and the development of practical regulations that achieve goals of safety and environmental protection without compromising the development of Texas' natural resources.

Should you have any questions please contact Mari Ruckel at mruckel@txoga.org or 512/478-6631.

Sincerely,



Mari Ruckel
Vice President
Government and Regulatory Affairs
Texas Oil and Gas Association

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

§3.13. Casing, Cementing, Drilling, Well Control, and Completion Requirements.

(a) General.

(1) Intent. The operator is responsible for compliance with this section during all operations at the well. It is the Intent of all provisions of this section that casing be securely anchored in the hole in order to effectively control the well at all times, all usable-quality water zones be isolated and sealed off to effectively prevent contamination or harm, and all [~~potentially~~] productive zones, potential flow zones, and zones with corrosive formation fluids be isolated and sealed off to prevent vertical migration of fluids or gases behind the casing. When the section does not detail specific methods to achieve these objectives, the responsible party shall make every effort to follow the intent of the section, using good engineering practices and the best currently available technology.

(2) Definitions. The following words and terms, when used in this section [~~chapter~~], shall have the following meanings, unless the context clearly indicates otherwise.

(A) Stand under pressure--To leave the hydrostatic column pressure in the well acting as the natural force without adding any external pump pressure. The provisions are complied with if a float collar and/or float shoe is used and found to be holding at the completion of the cement job.

(B) Zone of critical cement--

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

(l) For surface casing strings, ~~[shall be]~~ the bottom 20% of the casing string, ~~but shall be~~ no more than 1,000 feet nor less than 300 feet. The zone of critical cement extends to the land surface for surface casing strings of 300 feet or less.

Comment [CT1]: Grammatical correction.

(l) For intermediate or production casing strings, the bottom 20% of the casing string or not less than 300 vertical feet above the casing shoe or top of the highest proposed productive zone.

(C) Protection depth--Depth to which usable-quality water must be protected, as determined by the Groundwater Advisory Unit of the Oil and Gas Division ~~[Texas Commission on Environmental Quality (TCEQ) or its successor agencies]~~, which may include zones that contain brackish or saltwater if such zones are correlative and/or hydrologically connected to zones that contain usable-quality water.

(D) Productive zone ~~[horizon]~~--Any stratum known to contain oil, gas, or geothermal resources in commercial quantities in the area.

(E) Associated gas zone--A zone in an oil well in which natural gas, commonly known as gas cap gas, overlies and is in contact with crude oil in a reservoir.

(F) Bay well--Any well under the jurisdiction of the Commission for which the surface location is either:

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

(f) located in or on a lake, river, stream, canal, estuary, bayou, or other inland navigable waters of the state and which requires plugging by means other than conventional land-based methods, including, but not limited to, use of a barge, use of a boat, dredging, or building a causeway or other access road to bring in the necessary equipment to plug the well; or

(l) located on state lands seaward of the mean high tide line of the Gulf of Mexico in water of a depth at mean high tide of not more than 100 feet that is sheltered from the direct action of the open seas of the Gulf of Mexico.

(G) Deputy director of Field Operations--The deputy director of Field Operations of the Oil and Gas Division or the deputy director's delegate.

(H) Director--The director of the Oil and Gas Division of the Railroad Commission of Texas or the director's delegate.

(I) District director--The Director of a Railroad Commission district office or the district director's delegate.

(J) Hydraulic fracturing treatment--A completion process involving treatment of a well by the application of hydraulic fracturing fluid under pressure for the express purpose of initiating and/or propagating fractures in a target geologic formation to enhance production of oil

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

and/or natural gas.

(K) Land well--Any well subject to Commission jurisdiction for which the surface location is not in or on inland or coastal waters.

(L) Minimum separation well-- a well in which hydraulic fracturing treatments will be conducted and for which:

(i) the vertical distance between the base of usable quality water and the top of the formation to be stimulated is less than 1,000 vertical feet;

(ii) the director has determined contains inadequate separation between the base of usable quality water and the top of the formation in which hydraulic fracturing treatments will be conducted; or

(iii) the director has determined is in a structurally complex geologic setting.

(M) Offshore well--Any well subject to Commission jurisdiction for which the surface location is on state lands in or on the Gulf of Mexico, that is not a bay well.

(N) Potential flow zone--A zone designated and published in writing by the director, using data identified or developed by the Commission or proposed by the operator that needs to be isolated to prevent sustained pressurization of the surface casing/intermediate casing

Comment [CT2]: Revisions suggested for clarity.

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

~~or production casing annulus sufficient to cause damage to casing and/or cement in a well such that it presents a threat to subsurface water or other subsurface resources, or sufficient to cause the fluids in the annulus to maintain a static fluid level at or less than 250 vertical feet below the protection depth.~~

Comment [CT3]: TxOGA suggests deleting this language as it is unnecessary and infers that normal pressure is a hazard.

(O) Zone with corrosive formation fluids--Any zone containing formation fluids that are capable of negatively impacting the integrity of casing and/or cement or have a demonstrated trend of failure for similar casing and cement design in the field.

(3) Wellbore diameters.

(A) The diameter of the wellbore in which surface casing will be set and cemented shall be at least one and one-half (1.50) inches greater than the nominal outside diameter of casing to be installed, unless otherwise approved by the district director.

(B) For subsequent casing strings, the diameter of each section of the wellbore for which casing will be set and cemented shall be at least one (1) inch greater than the nominal outside diameter of the casing to be installed, unless otherwise approved by the district director.

(C) The casing diameter requirements in subparagraphs (A) and (B) do not apply to reentries, liners, and expandable casing.

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

(D) The wellbore diameter shall be consistent with manufacturer's recommendations for all float equipment; centralizers, packers, cement baskets, and all other equipment run into the wellbore on casing.

(4) Casing and cementing.

(A) All casing cemented in any well shall be steel casing that has been hydrostatically pressure tested with an applied pressure at least equal to the maximum pressure to which the pipe will be subjected in the well. For new pipe, the mill test pressure may be used to fulfill this requirement. As an alternative to hydrostatic testing, a casing evaluation tool may be employed. Casing meeting the performance standards set forth in API Specification 5CT: Specification for Casing and Tubing (or a Commission-approved equivalent standard) shall be used through the protection depth.

(B) The base cement shall meet the standards set forth in API Specification 10A: Specification for Cement and Material for Well Cementing or the American Society for Testing and Materials (ASTM) Specification C150/C150M, Standard Specification for Portland Cement (or a Commission-approved equivalent standard).

(C) Casing shall be cemented across and above all formations permitted for injection under §3.9 of this title (relating to Disposal Wells), or §3.46 of this title (relating to Fluid

Comment [CT4]: Adding the term "base" allows the use of API cement/fly ash or ASTM cement/ fly ash blends and is consistent with the definition of "base" used by ASTM; these blends are used on virtually every well in the state.

**TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)**

Injection Into Productive Reservoirs), within one-quarter mile of the proposed well location, in the following manner:

(i) If the top of cement is determined through calculation, across and extending at least 600 feet (measured depth) above the permitted formations;

(ii) If the top of cement is determined through the performance of a temperature survey, across and extending 250 feet (measured depth) above the permitted formations;

(iii) If the top of cement is determined through the performance of a cement evaluation log, across and extending 100 feet (measured depth) above the permitted formations;

(iv) across and extending at least 200 feet into the previous casing shoe (or to surface if the shoe is less than 200 feet from the surface); or

(v) as otherwise approved by the district director.

(D) Casing shall be cemented across and above all productive zones, potential flow zones, and/or zones with corrosive formation fluids, in the following manner:

(i) If the top of cement is determined through calculation, across and extending at least 600 feet (measured depth) above the zones;

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

(II) If the top of cement is determined through the performance of a temperature survey, across and extending 250 feet (measured depth) above the zones;

(III) if the top of cement is determined through the performance of a cement evaluation log, across and extending 100 feet (measured depth) above the zones;

(IV) across and extending at least 200 feet into the previous casing shoe (or to the surface if the shoe is less than 200 feet from the surface); or

(v) as otherwise approved by the district director.

(E) Where necessary, the cement slurry shall be designed to control annular gas migration consistent with, or equivalent to, the standards in API Standard 65-Part 2: Isolating Potential Flow Zones During Well Construction.

(5) Casing testing before drillout. For surface and intermediate strings of casing, before drilling the cement plug, the operator shall test the casing at a pump pressure in pounds per square inch (psi) calculated by multiplying the length of the true vertical depth in feet of the casing string by a factor of 0.5 psi per foot. The maximum test pressure required, however, unless otherwise ordered by the commission, need not exceed 1,500 psi. If, at the end of 30 minutes, the pressure shows a drop of 10% or more from the original test pressure, the casing shall be condemned until the leak is corrected. A pressure test demonstrating less than a 10% pressure

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

drop after 30 minutes constitutes confirmation that the condition has been corrected. The operator shall notify the district director of a failed test. In the event of a pressure test failure, completion operations may not re-commence until the district director approves a remediation plan, the operator successfully implements the plan, and the operator conducts a successful pressure test.

(6) Well control.

(A) Wellhead assemblies. After setting the conductor pipe and/or surface

casing, wellhead assemblies shall be used on wells to maintain surface control of the well at all times. Each component of the wellhead shall have a pressure rating equal to or greater than the anticipated pressure to which that particular component might be exposed during the course of drilling, testing, or producing the well.

Comment [CT5]: This language is unnecessary with the revisions to (6)(B)

(B) Well control equipment.

(i) An operator shall install a blowout preventer system or control head and other connections to keep the well under control at all times as soon as surface casing is set. When conductor casing is set and/or shallow gas is anticipated to be encountered, operators shall install a diverter system on the conductor casing. For bay and offshore wells, at a minimum, such systems shall include a double ram blowout preventer, including pipe and blind rams, an annular-type blowout preventer or other equivalent control system, and a shear ram.

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

(II) For wells in areas with hydrogen sulfide, the operator shall
comply with §3.36 of this title (relating to Oil, Gas, or Geothermal Resource Operation in
Hydrogen Sulfide Areas).

(III) Ram type blowout prevention equipment shall have a rated
working pressure that equals or exceeds the maximum anticipated surface pressure of the well.
Blowout preventer rams shall be of a proper size for the drill pipe being used or production casing
being run in the well or shall be variable-type rams that are in the appropriate size range.
Alternatively, an annular preventer may be used in lieu of casing/pipe rams or variable bore rams
when running production casing provided the expected shut-in surface pressures would not
exceed the tested pressure rating of the annular preventer.

(iv) Controls shall be accessible on the rig floor or at a safe remote
location.

(v) Operators shall install a drill pipe safety valve to close off the
drill pipe to prevent backflow of water, oil, gas, or other formation fluids into the drill string
wellbore during drilling.

(vi) Operators shall install a choke line of the sufficient size and
working pressure.

Comment [CT6]: Depending on the make/model of BOP stacks provided by the drilling contractors, variable-type rams may be not available and if they are available the range capacity may not be suitable to cover the drill pipe and production casing sizes being used (i.e. 4" to 5-1/2" or 7"). The annular preventers are normally rated/tested well within the range of well control situations and are suitable for drill pipe, drill collars, or the production casing. The additional language allows for the use of annular preventer and provides a secondary means of control in the event the annular preventer leaks or wears out by being able to close the pipe rams at bottom.

Comment [CT7]: Revisions suggested for technical accuracy.

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

(vii) When using a Kelly rig during drilling, the well shall be fitted with an upper Kelly cock in proper working order to close in the drill string below hose and swivel, when necessary for well control. A lower Kelly safety valve shall be installed so that it can be run through the blowout preventer. When needed for well control, the operator shall maintain at all times on the rig floor safety valves to include:

(I) full-opening safety valve; and

(II) inside blowout preventer valve with wrenches, handling tools, and necessary subs for all drilling pipe sizes in use.

(viii) All well control equipment shall be consistent with API Standard 53: Recommended Practices for Blowout Prevention Equipment Systems for Drilling Wells. Control equipment shall be certified in accordance with API Standard 53 as operable under the product manufacturer's minimum operational specifications. Certification shall include the proper operation of the closing unit valving, the pressure gauges, and the manufacturer's recommended accumulator fluids. Certification shall be obtained through an independent company that tests blowout preventers, stacks and casings. Certification shall be performed every five (5) years and the proof of certification shall be made available upon request of the Commission.

(ix) All well control equipment shall be in good working condition at

Comment [CT8]: Revision suggested for technical accuracy.

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

all times. All outlets, fittings, and connections on the casing, blowout preventers, choke manifold, and auxillary wellhead equipment that may be subjected to wellhead pressure shall be of a material and construction to withstand or exceed the anticipated pressure. The lines from outlets on or below the blowout preventers shall be securely installed, anchored, and protected from damage.

(x) In addition to the primary closing system, including an accumulator system, the blowout preventers shall have a secondary location for ~~mode of closure.~~ at a remote location.

Comment [CT9]: Revision suggested for technical accuracy

(xi) Testing of blowout prevention equipment.

(I) Ram type blowout prevention equipment shall be tested to at least the maximum anticipated surface pressure of the well, but not less than 1,500 psi, before drilling the plug on the surface casing and ~~before encountering any high pressure formations.~~

Comment [CT10]: Operators are already on a testing frequency and as proposed, this language infers that an operator would have to stop and test again

(II) Blowout prevention equipment shall be tested upon installation, after the disconnection or repair of any pressure containment seal in the blowout preventer stack, choke line, or choke manifold, limited to the affected component, with testing to occur at least every 21 days. When requested, the district director shall be notified before the

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

commencement of a test.

(III) A record of each test, including test pressures, times, failures, and each mechanical test of the casings, blowout preventers, surface connections, surface fittings, and auxiliary wellhead equipment shall be entered in the logbook, signed by the person responsible for the test, and made available for inspection by the commission upon request.

(C) Drilling fluid program.

(I) The characteristics, use, and testing of drilling fluid and conduct of related drilling procedures shall be designed to prevent the blowout of any well. Adequate supplies of drilling fluid of sufficient weight and other acceptable characteristics shall be maintained. Drilling fluid tests shall be performed as needed to ensure well control. Adequate drilling fluid testing equipment shall be kept on the drilling location at all times. The hole shall be filled with sufficient drilling fluid to maintain well control at all times. When pulling drill pipe, the drilling fluid volume required to fill the hole each time shall be measured to assure that it corresponds with the displacement of pipe pulled. Mud pit levels shall be monitored during the drilling process. Mud-gas separation equipment shall be installed and operated as needed when abnormally pressured gas-bearing formations may be encountered. The commission shall have

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

access to the drilling fluid records and shall be allowed to conduct any essential tests on the drilling fluid used in the drilling or recompletion of a well. When the conditions and tests indicate a need for a change in the drilling fluid program in order to insure control of the well, the operator shall use due diligence in modifying the program.

(I) Wells drilled with air shall maintain well control using blowout preventer systems and/or diverter systems.

(II) All hole intervals drilled prior to reaching the base of protected water shall be drilled with air, fresh water or a fresh water based drilling fluid. No oil-based drilling fluid may be used until casing has been set and cemented to the protection depth.

(D) Diverter systems for bay and offshore wells. Any bay or offshore well that is drilled to and/or through formations where the expected reservoir pressure exceeds the hydrostatic pressure of the drilling fluid column shall be equipped to divert any wellbore fluids away from the rig floor. When the diverter system is installed, the diverter components including the sealing element, diverter valves, control systems, stations and vent lines shall be function and pressure tested. For drilling operations with a surface wellhead configuration, the system shall be function tested at least once every 24-hour period after the initial test. After all connections have been made on the surface casing or conductor casing, the diverter sealing element and diverter

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

valves shall be pressure tested to a minimum of 200 psig. Subsequent pressure tests shall be conducted within seven days after the previous test. All diverter systems shall be maintained in working condition. No operator shall continue drilling operations if a test or other information indicates that the diverter system is unable to function or operate as designed.

(E) Casinghead.

(i) Requirements. All land and bay wells shall be equipped with casingheads of sufficient rated working pressure, with adequate connections and valves accessible at the surface, to allow pumping of fluid between any two strings of casing at the surface.

(ii) Casinghead test procedure. Any well showing sustained pressure on the casinghead, or leaking gas or oil between the surface casing and the next casing string, shall be tested in the following manner. The well shall be killed with water or mud and pump pressure applied. The casing shall be condemned if the pressure gauge on the casinghead reflects the applied pressure. After completing corrective measures, the casing shall be tested in the same manner. This method shall be used when the origin of the pressure cannot otherwise be determined.

(F) Christmas tree.

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

(I) All completed non-pumping wells shall be equipped with Christmas tree fittings and wellhead connections with a rated working pressure equal to, or greater than, the surface shut-in pressure of the well. The tubing shall be equipped with a master valve, but two master valves shall be used on all wells with surface pressures in excess of 5,000 psi. All wellhead connections shall be assembled and tested prior to installation by a fluid pressure equal to the test pressure of the fitting employed.

(II) The Christmas tree for completed bay and offshore wells shall be equipped with either two master valves, one master valve and one wing valve, or two wing valves. All bay and offshore wells shall have at least five feet of spacing between the bottom of the Christmas tree and the surface of the water at high tide, where applicable. Any newly completed bay and offshore well or existing well on which the Christmas tree is being replaced shall be equipped with a back pressure valve wellhead profile at the flange where the tubing hangs on the Christmas tree.

(G) Storm choke and safety valve.

(I) Bay and offshore wells shall be equipped with a storm choke and/or safety valve installed in the tubing.

(II) An operator may request approval to use a surface safety valve

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

In lieu of a subsurface safety valve by filing with the appropriate district director a written request for such approval providing all pertinent information to support the exception.

(iii) The depth and type of the safety valve shall be reported in the "remarks" section of the appropriate completion report form required by §3.16 of this title (relating to Log and Completion or Plugging Report), after the well is completed or recompleted.

(7) Additional requirements for wells on which hydraulic fracturing treatments will be conducted.

(A) All casing installed in a well that will be subjected to hydraulic fracturing treatments shall have a minimum internal yield pressure rating of at least 1.10 ~~4.15~~ times the maximum pressure to which the casing may be subjected.

Comment [CT11]: 1.10 is industry standard; the manufacturer already includes a safety factor in their ratings and the addition is not justified, the cost of change would be significant.

(B) The operator shall pressure test the casing (or fracture tubing) on which the pressure will be exerted during hydraulic fracturing treatments to at least the maximum anticipated pressure. The casing required to be pressure tested shall be from the wellhead to the depth of the surface casing shoe or the top of calculated cement of the casing being tested, whichever is deeper. Casing strings, that include a pressure actuated valve or sleeve shall be tested to 80% of valve actuation pressure for a minimum time period of 5 minutes. A surface pressure loss of greater than 10% of initial test pressure is considered a failed test. The district

Comment [CT12]: Clarifies which part of the casing needs to be tested.

Comment [CT13]: Clarifies that currently used technology (i.e. casing strings with toe shoe or similar) may continue to be used.

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

director shall be notified of a failed test within 24 hours of completion of the test. In the event of a pressure test failure, no hydraulic fracturing treatment may be conducted until the district director has approved a remediation plan, and the operator has implemented the approved remediation plan and successfully re-tested the casing (or fracture tubing).

Comment [CT14]: Revision suggested for clarity.

(C) During hydraulic fracturing treatment operations, the operator shall monitor all annuli. The operator shall immediately suspend hydraulic fracturing treatment operations if the pressures deviates above those anticipated increases caused by pressure or thermal transfer and shall notify the appropriate district director within 24 hours of such deviation. Further completion operations, including hydraulic fracturing treatment operations, may not recommence until the district director approves a remediation plan and the operator successfully implements the approved plan.

(D) The following conditions also apply if the well is a minimum separation well, unless otherwise approved by the director:

(i) Cementing of the production casing in a minimum separation well shall be by the pump and plug method. The production casing shall be cemented from the shoe up to a point at least 200 feet (measured depth) above the shoe of the next shallower casing string that was set and cemented in the well (or to surface if the shoe is less than 200 feet from

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

the surface).

(ii) The operator shall pressure test the casing string on which the pressure will be exerted during stimulation to the maximum pressure that will be exerted during hydraulic fracturing treatment. The operator shall notify the district director within 24 hours of a failed test. In the event of a pressure test failure no hydraulic fracturing treatment may be conducted until the district director has approved a remediation plan, and the operator has implemented the approved remediation plan and successfully re-tested the casing (or fracture tubing).

(iii) The production casing for any minimum separation well shall not be disturbed for a minimum of eight hours after cement is in place and casing is hung-off, and in no case shall the casing be disturbed until the cement has reached a minimum compressive strength of 500 psi.

(iv) In addition to conducting an evaluation of cementing records and annular pressure monitoring results, the operator of a minimum separation well shall run a cement evaluation tool to assess radial cement integrity and placement behind the production casing. If the cement evaluation indicates insufficient isolation, completion operations may not re-commence until the district director approves a remediation plan and the operator successfully

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

Implements the approved plan.

(v) The operator of a minimum separation well may request from the appropriate district director approval of an exemption from the requirement to run a cement evaluation tool. Such request shall include information demonstrating that the operator has:

(i) successfully set, cemented, and tested the casing for which the exemption is requested in at least five minimum separation wells by the same operator in the same operating field;

(ii) obtained cement evaluation tool logs that support the findings of cementing records, annular pressure monitoring results or other tests demonstrating that successful cement placement was achieved to isolate productive zones, potential flow zones, and/or zones with corrosive formation fluids; and

(iii) shown that the well for which the exemption is requested will be constructed and cemented using the same or similar techniques, methods, and cement formulation used in the five wells that have had successful cement jobs.

(8) Pipeline shut-off valves for bay and offshore wells. All bay and offshore gathering pipelines designed to transport oil, gas, condensate, or other oil or geothermal resource field fluids from a well or platform shall be equipped with automatically controlled shut-off valves

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

at critical points in the pipeline system. Other safety equipment shall be in full working order as a safeguard against spillage from pipeline ruptures.

(9) Training for bay and offshore wells. All tool pushers, drilling superintendents, and operators' representatives (when the operator is in control of the drilling) shall be required to, upon request, furnish certification of satisfactory completion of an American Petroleum Institute (API) training program, an International Association of Drilling Contractors (IADC) training program, or other equivalent nationally recognized training program on well control equipment and procedures. The certification shall be renewed every two years by attending an API- or IADC-approved refresher course or a refresher course approved by the equivalent nationally recognized training program.

(10) Bottom-hole pressure surveys. The commission may require bottom-hole pressure surveys of the various fields at such times as determined to be necessary. However, operators shall be required to take bottom-hole pressures only in those wells that are not likely to suffer damaging effects from the survey. Tubing and tubingheads shall be free from obstructions in wells used for bottom-hole pressure test purposes.

(b) Casing and cementing requirements for land wells and bay wells [Onshore and inland waters].

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

~~[(1) General.]~~

~~[(A) All casing cemented in any well shall be steel casing that has been hydrostatically pressure tested with an applied pressure at least equal to the maximum pressure to which the pipe will be subjected in the well. For new pipe, the mill test pressure may be used to fulfill this requirement. As an alternative to hydrostatic testing, a full length electromagnet, ultrasonic, radiation thickness gauging, or magnetic particle inspection may be employed.]~~

~~[(B) Wellhead assemblies shall be used on wells to maintain surface control of the well. Each component of the wellhead shall have a pressure rating equal to or greater than the anticipated pressure to which that particular component might be exposed during the course of drilling, testing, or producing the well.]~~

~~[(C) A blowout preventer or control head and other connections to keep the well under control at all times shall be installed as soon as surface casing is set. This equipment shall be of such construction and capable of such operation as to satisfy any reasonable test which may be required by the commission or its duly accredited agent.]~~

~~[(D) When cementing any string of casing more than 200 feet long, before drilling the cement plug the operator shall test the casing at a pump pressure in pounds per square inch (psi) calculated by multiplying the length of the casing string by 0.2. The maximum test pressure~~

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

~~required, however, unless otherwise ordered by the commission, need not exceed 1,500 psi. If, at the end of 30 minutes, the pressure shows a drop of 10% or more from the original test pressure, the casing shall be condemned until the leak is corrected. A pressure test demonstrating less than a 10% pressure drop after 30 minutes is proof that the condition has been corrected.]~~

~~[(E) Wells drilling to formations where the expected reservoir pressure exceeds the weight of the drilling fluid column shall be equipped to divert any wellbore fluids away from the rig floor. All diverter systems shall be maintained in an effective working condition. No well shall continue drilling operations if a test or other information indicates the diverter system is unable to function or operate as designed.]~~

(1) ~~[(2)]~~ Surface casing requirements for land wells and bay wells.

(A) Any proposal to set surface casing to a depth of 3,500 feet or greater shall require prior approval of the appropriate district director. A request for such approval shall be in writing and shall specify how the operator plans to maintain well control during drilling, and ensure successful circulation and adequate bonding of cement, and, if necessary, prevent upward migration of deeper formation fluids into protected water. The district director may grant approvals on an area basis.

(B) [(A)] Amount required.

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

(i) An operator shall set and cement sufficient surface casing to protect all usable-quality water strata, as defined by the Groundwater Advisory Unit of the Oil and Gas Division [TCEQ]. Unless surface casing requirements are specified in field rules approved prior to the effective date of this rule, before [~~Before~~] drilling any well [~~in any field or area in which no field rules are in effect or in which surface casing requirements are not specified in the applicable field rules~~], an operator shall obtain a letter from the Groundwater Advisory Unit of the Oil and Gas Division [TCEQ] stating the protection depth. In no case, however, is surface casing to be set deeper than 200 feet below the specified depth without prior approval from the district director [~~commission~~]. The district director may grant such approval on an area basis.

(ii) Any well drilled to a total depth of 1,000 feet or less below the ground surface may be drilled without setting surface casing provided no shallow gas sands or abnormally high pressures are known to exist at depths shallower than 1,000 feet below the ground surface; and further, provided that production casing is cemented from the shoe to the ground surface by the pump and plug method.

(C) [B] Cementing. Cementing shall be by the pump and plug method.

Sufficient cement shall be used to fill the annular space outside the casing from the shoe to the ground surface or to the bottom of the cellar. If cement does not circulate to ground surface or the bottom of

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

the cellar, the operator or the operator's [his] representative shall obtain the approval of the district director for the procedures to be used to perform additional cementing operations, if needed, to cement surface casing from the top of the cement to the ground surface.

(D) [~~(C)~~] Cement quality.

(i) Surface casing strings must be allowed to stand under pressure until the cement has reached a compressive strength of at least 500 psi in the zone of critical cement before drilling plug or initiating a test. The cement mixture in the zone of critical cement shall have a 72-hour compressive strength of at least 1,200 psi.

(ii) An operator may use cement with volume extenders above the zone of critical cement to cement the casing from that point to the ground surface, but in no case shall the cement have a compressive strength of less than 100 psi at the time of drill out nor less than 250 psi 24 hours after being placed.

(iii) In addition to the minimum compressive strength of the cement, the free water content shall be minimized to the greatest extent practicable in the cement slurry to be used in the zone of critical cement. In no event shall the [API] free water separation [shall] average [no] more than two milliliters [~~six milliliters~~] per 250 milliliters of cement tested in accordance with the current API RP 10B-2: Recommended Practice for Testing Well Cements, inside the zone

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

of critical cement, or more than six milliliters per 250 milliliters of cement tested outside the zone of critical cement [10B].

(iv) The commission may require a better quality of cement mixture to be used in any well or any area if ~~[evidence of leak]~~ conditions indicate that ~~[indicates]~~ a better quality of cement is necessary to prevent pollution, isolate productive zones, potential flow zones, or zones with corrosive formation fluids or prevent a safety issue in the well ~~[or to provide safer conditions in the well or area].~~

~~(E) [10B]~~ Compressive strength tests. Cement mixtures for which published performance data are not available must be tested by the operator or service company. Tests shall be made on representative samples of the basic mixture of cement and additives used, using distilled water or potable tap water for preparing the slurry. The tests must be conducted using the equipment and procedures in, or equipment and procedures equivalent to those in, API RP 10B-2, Recommended Practice for Testing Well Cements ~~[adopted by the American Petroleum Institute, as published in the current API RP 10B].~~ Test data showing competency of a proposed cement mixture to meet the above requirements must be furnished to the commission prior to the cementing operation. To determine that the minimum compressive strength has been obtained, operators shall use the typical performance data for the particular cement used in the well (containing all the additives, including any accelerators used

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

in the slurry) at the following temperatures and at atmospheric pressure.

(I) For the cement in the zone of critical cement, the test temperature shall be within 10 degrees Fahrenheit of the formation equilibrium temperature at the top of the zone of critical cement.

(II) For the filler cement, the test temperature shall be the temperature found 100 feet below the ground surface level, or 60 degrees Fahrenheit, whichever is greater.

(F) [~~E~~] Cementing report. Within 30 days of [Open] completion of the well, or within 90 days of cessation of drilling operations, whichever is earlier, a cementing report must be filed with the commission furnishing complete data concerning the cementing of surface casing in the well as specified on a form furnished by the commission. The operator of the well or the operator's [his] duly authorized agent having personal knowledge of the facts, and representatives of the cementing company performing the cementing job, must sign the form attesting to compliance with the cementing requirements of the commission.

(G) [~~F~~] Centralizers. Surface casing shall be centralized at the shoe, above and below a stage collar or diverting tool, if run, and through usable-quality water zones. In nondeviated holes, pipe centralization as follows is required: a centralizer shall be placed every fourth joint from the cement shoe to the ground surface or to the bottom of the cellar. All centralizers shall meet specifications

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

In, or equivalent to, API spec 10D Specifications for Bow-Spring Casing Centralizers; API Spec 10

TR4, Technical Report on Considerations Regarding Selection of Centralizers for Primary

Cementing Operations; and API RP 10D-2, Recommended Practice for Centralizer Placement

and Stop Collar Testing [specifications]. In deviated holes, the operator shall provide additional centralization.

(H) [~~(G)~~] Alternative surface casing programs.

(i) An alternative method of fresh water protection may be approved upon written application to the appropriate district director. The operator shall state the reason [~~(economics, well control, etc.)~~] for the alternative fresh water protection method and outline the alternate program for casing and cementing through the protection depth for strata containing usable-quality water. Alternative programs for setting more than specified amounts of surface casing for well control purposes may be requested on a field or area basis. Alternative programs for setting less than specified amounts of surface casing will be considered [authorized] on an individual well basis only. The district director may approve, modify, or reject the proposed program. The district director shall deny the request if the operator has not demonstrated that the alternative casing plan will achieve the intent of this rule as described in subsection (a)(1) of this section. If the proposal is modified or rejected, the operator may request a review by the deputy director of field operations. If

**TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)**

the proposal is not approved administratively, the operator may request a public hearing. An operator shall obtain approval of any alternative program before commencing operations.

(ii) Any alternate casing program shall require the first string of casing set through the protection depth to be cemented in a manner that will effectively prevent the migration of any fluid to or from any stratum exposed to the wellbore outside this string of casing. The casing shall be cemented from the shoe to ground surface in a single stage, if feasible, or by a multi-stage process with the stage tool set at least 100 [50] feet below the protection depth.

(iii) Any alternate casing program shall include pumping sufficient cement to fill the annular space from the shoe or multi-stage tool to the ground surface. If cement is not circulated to the ground surface or the bottom of the cellar, the operator shall run a temperature survey or cement bond log. The appropriate district office shall be notified prior to running the required temperature survey or bond log. After the top of cement outside the casing is determined, the operator or the operator's [his] representative shall contact the appropriate district director and obtain approval for the procedures to be used to perform any required additional cementing operations. Upon completion of the well, a cementing report shall be filed with the commission on the prescribed form.

(iv) Before parallel (nonconcentric) strings of pipe are cemented in a well, surface or intermediate casing must be set and cemented through the protection depth.

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

(I) Mechanical integrity test of surface casing after drillout.

(i) If the surface casing is exposed to more than 360 rotating hours after reaching total depth or the depth of the next casing string, the operator shall verify the integrity of the surface casing by using a casing evaluation tool or conducting a mechanical integrity test or equivalent Commission-approved casing evaluation method, unless otherwise approved by the district director.

(ii) If a mechanical integrity test is conducted, the appropriate district office shall be notified at least eight hours before the test is conducted to give the district office an opportunity to witness the test. The operator shall use a chart of acceptable range (20% - 80% of full scale) or an electronic equivalent approved by the district director, and the surface casing shall be tested at a pump pressure in pounds per square inch (psi) calculated by multiplying the length of the true vertical depth in feet of the casing string by a factor of 0.5 psi per foot up to a maximum of 1,500 psi for a minimum of 30 minutes. A pressure test demonstrating less than a 10% pressure drop after 30 minutes constitutes confirmation of an acceptable pressure test. The appropriate district office shall be notified within 24 hours after a failed test. Completion operations may not re-commence until the district director approves a remediation plan and the operator successfully implements the approved plan, and successfully

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

re-tests the surface casing.

(2) [~~3~~] intermediate casing requirements for land wells and bay wells.

(A) Cementing method. Each intermediate string of casing shall be cemented from the shoe to a point at least 600 feet (measured depth) above the shoe. If any productive zone, potential flow zone, or zone with corrosive formation fluids [~~horizon~~] is open to the wellbore above the casing shoe, the casing shall be cemented;

(i) if the top of cement is determined through calculation, from the shoe up to a point at least 600 feet (measured depth) above the top of the shallowest productive zone, potential flow zone, or zone with corrosive formation fluids; [~~horizon~~]

(ii) if the top of cement is determined through performance of a temperature survey, from the shoe up to a point at least 250 feet (measured depth) above the top of the shallowest productive zone, potential flow zone, or zone with corrosive formation fluids;

(iii) if the top of cement is determined through performance of a cement evaluation log, from the shoe up to a point at least 100 feet (measured depth) above the top of the shallowest productive zone, potential flow zone, or zone with corrosive formation fluid;

or

(iv) [~~er~~] to a point at least 200 feet (measured depth) above the shoe

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

of the next shallower casing string that was set and cemented in the well (or to surface if the shoe is less than 200 feet from the surface); or

(v) as otherwise approved by the district director.

(B) Top of cement. The calculated or measured top of cement shall be indicated on the appropriate completion form required by §3.16 of this title (relating to Log and Completion or Plugging Report).

(C) [(B)] Alternate method. In the event the distance from the casing shoe to the top of the shallowest productive zone, potential flow zone, and/or zone with corrosive formation fluids [~~horizon~~] make cementing, as specified above, impossible or impractical, the multi-stage process may be used to cement the casing in a manner that will effectively isolate and seal the zones to [~~off all such possible productive horizons and~~] prevent fluid migration to or from such strata within the wellbore.

(3) [(4)] Production casing requirements for land wells and bay wells.

(A) Centralizers. In deviated and horizontal holes, the operator shall provide additional centralization as necessary to ensure zonal isolation between the top of the interval to be completed and the shallower zones that require isolation.

(B) Cementing method. The production [~~producing~~] string of casing shall be

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

cemented by the pump and plug method, or another method approved by the commission, with sufficient cement to fill the annular space back of the casing to the surface or to a point at least 600 feet above the shoe. If any productive zone, potential flow zone and/or zone with corrosive formation fluids [~~horizon~~] is open to the wellbore above the casing shoe, the casing shall be cemented in a manner that effectively seals off all such zones [~~possibly productive horizons~~] by one of the methods specified for intermediate casing in paragraph (2) [~~(3)~~] of this subsection. A float collar or other means to stop the cement plug shall be inserted in the casing string above the shoe. Cement shall be allowed to stand under pressure for a minimum of eight hours before drilling the plug or initiating casing pressure tests. In the event that the distance from the casing shoe to the top of the shallowest productive zone, potential flow zone and/or zone with corrosive formation fluids make cementing, as required above, impossible or impractical, the multi-stage process may be used to cement the casing in a manner that will effectively seal off all such zones, and prevent fluid migration to or from such zones within the wellbore. Uncemented casing is allowable within a producing reservoir provided the production casing is cemented in such a manner to effectively isolate and seal off that zone from all other productive zones in the wellbore as required by §3.7 of this title (relating to Strata To Be Sealed Off).

Comment [CT15]: Revision suggested for clarity.

(C) Reporting of top of cement. Calculated or measured top of cement shall

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

be indicated on the appropriate completion form required by §3.16 of this title.

(D) [~~(B)~~] Isolation of associated gas zones. The position of the gas-oil contact shall be determined by coring, electric log, or testing. The producing string shall be landed and cemented below the gas-oil contact, or set completely through and perforated in the oil-saturated portion of the reservoir below the gas-oil contact.

(4) [~~(5)~~] Tubing [~~and stem-check~~] requirements for land wells and bay wells.

(A) Tubing requirements for oil wells. All flowing oil wells shall be equipped with and produced through tubing. When tubing is run inside casing in any flowing oil well, the bottom of the tubing shall be at a point not higher than 100 feet (vertical depth) above the top of the producing interval nor more than 50 feet (vertical depth) above the top of the liner [a-line], if a liner [one] is used, or 100 feet (vertical depth) above the kickoff point in a deviated or horizontal well. In a multiple zone structure, however, when an operator elects to equip a well in such a manner that small through-the-tubing type tools may be used to perforate, complete, plug back, or recomplete without the necessity of removing the installed tubing, the bottom of the tubing may be set at a distance up to, but not exceeding, 1,000 feet (vertical depth) above the top of the perforated or open-hole interval actually open for production into the wellbore. [~~in no case shall tubing be set at a depth of less than 70% of the distance from the surface of the ground to the top of the interval actually open to production.~~]

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

(B) Alternate tubing requirements. Alternate programs requesting a temporary exception pursuant to subsection (d) of this section to omit tubing from a flowing oil well may be authorized on an individual well basis by the appropriate district director. The district director shall deny the request if the operator has not demonstrated that the alternative tubing plan will achieve the intent as described in subsection (a)(1) of this section. If the proposal is rejected, the operator may request a review by the director of field operations. If the proposal is not approved administratively, the operator may request a hearing. An operator shall obtain approval of any alternative program before commencing operations.

~~[(B) Storm choke. All flowing oil, gas, and geothermal resource wells located in bays, estuaries, lakes, rivers, or streams must be equipped with a storm choke or similar safety device installed in the tubing a minimum of 100 feet below the mud line.]~~

(c) Casing, cementing, drilling, and completion requirements for offshore wells ~~[Texas-offshore casing, cementing, drilling, and completion requirements].~~

(1) Casing. An offshore well shall be cased with ~~[The casing program shall include]~~ at least three strings of pipe, in addition to such drive pipe as the operator may desire, which shall be set in accordance with the following program.

(A) Conductor casing. A string of new pipe, or reconditioned pipe with

**TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)**

substantially the same characteristics as new pipe, shall be set and cemented at a depth of not less than 300 feet TVD (true vertical depth) nor more than 800 feet TVD below the mud line. Sufficient cement shall be used to fill the annular space back of the pipe to the mud line; however, cement may be washed out or displaced to a maximum depth of 50 feet below the mud line to facilitate pipe removal on abandonment. Casing shall be set and cemented in all cases prior to penetration of known shallow oil and gas formations, or upon encountering such formations.

(B) Surface casing. All surface casing shall be a string of new pipe with a mill test of at least 1,100 pounds per square inch (psi) or reconditioned pipe that has been tested to an equal pressure. Sufficient cement shall be used to fill the annular space behind the pipe to the mud line; however, cement may be washed out or displaced to a maximum depth of 50 feet below the mud line to facilitate pipe removal on abandonment. Surface casing shall be set and cemented in all cases prior to penetration of known shallow oil and gas formations, or upon encountering such formations. In all cases, surface casing shall be set prior to drilling below 3,500 feet TVD. Minimum depths for surface casing are as follows.

(i) Surface Casing Depth Table.

Figure: 16 TAC §3.13(c)(1)(B)(i)

--	--

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

Proposed Total Vertical Depth of Well	Surface
to 7,000 feet	25% of proposed total depth of well
7,000 - 10,000 feet	2,000 feet
10,000 and below	2,500 feet

(II) Surface Casing test.

(I) Cement shall be allowed to stand under pressure for a minimum of eight hours before drilling plug or initiating tests. Casing shall be tested by pump pressure to at least 1,000 psi. If, at the end of 30 minutes, the pressure shows a drop of 100 psi or more, the casing shall be condemned until the leak is corrected. A pressure test demonstrating a drop of less than 100 psi after 30 minutes constitutes confirmation [is-proof] that the condition has been corrected.

(II) After drillout, if the surface casing is exposed to more than 360 rotating hours, the operator shall verify the integrity of the casing using a casing evaluation tool, a mechanical integrity test, or an equivalent Commission-approved alternate casing evaluation methodology, unless otherwise approved by the district director.

(III) If a mechanical integrity test of the surface casing is conducted, the appropriate district office shall be notified a minimum of eight (8) hours before the test is conducted. The operator shall use a chart of acceptable range (20% - 80% of full scale) or

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

an electronic equivalent approved by the district director, and the surface casing shall be tested at a minimum test pressure of 0.5 psi per foot multiplied by the true vertical depth of the surface casing up to a maximum of 1,500 psi for a minimum of 30 minutes. A pressure test demonstrating less than a 10% drop in pressure after 30 minutes constitutes confirmation of an acceptable pressure test. The operator shall notify the appropriate district office within 24 hours of a failed test. Completion operations may not re-commence until the district director approves a remediation plan and the operator implements the approved plan, and the operator successfully re-tests the surface casing.

Comment [CT16]: Revision suggested for technical accuracy.

(C) Production casing or oil string.

(i) The production casing or oil string shall be new or reconditioned pipe with a mill test of at least 2,000 psi that has been tested to an equal pressure.

(ii) After [and after] cementing, the production casing shall be tested by pump pressure to at least 1,500 psi. If, at the end of 30 minutes, the pressure shows a drop of 150 psi or more, the casing shall be condemned. After corrective operations, the casing shall again be tested in the same manner.

(iii) Cementing of the production casing shall be by the pump and plug method. Sufficient cement shall be used to fill the calculated annular space above the shoe to isolate

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

~~[protect]~~ any productive zones, potential flow zones, or zones with corrosive formation fluids
~~[prospectively-producing horizons]~~ and to a depth that isolates abnormal pressure from normal pressure
(0.465 psi per vertical foot of gradient). A float collar or other means to stop the cement plug shall
be inserted in the casing string above the shoe. Cement shall be allowed to stand under pressure for
a minimum of eight hours before drilling the plug or initiating tests.

(2) Operators shall comply with the well control requirements of subsection (a)(6)
of this section.

~~[(2) Blowout preventers.]~~

~~[(A) Before drilling below the conductor casing, the operator shall install at least
one remotely controlled blowout preventer with a mechanism for automatically diverting the drilling fluid
to the mud system when the blowout preventer is activated.]~~

~~[(B) After setting and cementing the surface casing, a minimum of two remotely
controlled hydraulic ram-type blowout preventers (one equipped with blind rams and one with pipe
rams), valves, and manifolds for circulating drilling fluid shall be installed for the purpose of controlling
the well at all times. The ram-type blowout preventers, valves, and manifolds shall be tested to 100%
of rated working pressure, and the annular-type blowout preventer shall be tested to 1,000 psi at the
time of installation. During drilling and completion operations, the ram-type blowout preventers shall be~~

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

~~tested by closing at least once each trip, and the annular-type preventer shall be tested by closing on drill pipe once each week.]~~

~~[(3) Kelly cock. During drilling, the well shall be fitted with an upper kelly cock in proper working order to close in the drill string below hose and swivel, when necessary for well control. A lower kelly safety valve shall be installed so that it can be run through the blowout preventer. When needed for well control, the operator shall maintain at all times on the rig floor safety valves to include:]~~

~~[(A) full-opening valve of similar design as the lower kelly safety valves, and]~~

~~[(B) inside blowout preventer valve with wrenches, handling tools, and necessary subs for all drilling pipe sizes in use.]~~

~~[(4) Mud program. The characteristics, use, and testing of drilling mud and conduct of related drilling procedures shall be designed to prevent the blowout of any well. Adequate supplies of mud of sufficient weight and other acceptable characteristics shall be maintained. Mud tests shall be made frequently. Adequate mud testing equipment shall be kept on the drilling platform at all times. The hole shall be kept full of mud at all times. When pulling drill pipe, the mud volume required to fill the hole each time shall be measured to assure that it corresponds with the displacement of pipe pulled. A derrick floor recording mud-pit level indicator shall be installed and operative at all times. A careful watch for swabbing action shall be maintained when pulling out of hole. Mud-gas separation equipment~~

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

~~shall be installed and operated.]~~

~~[-(5) Casinghead.]~~

~~[(A) Requirement. All wells shall be equipped with casingheads of sufficient rated working pressure, with adequate connections and valves available, to permit pumping mud-laden fluid between any two strings of casing at the surface.]~~

~~[(B) Casinghead test procedure. Any well showing sustained pressure on the casinghead, or leaking gas or oil between the surface casing and the oil string, shall be tested in the following manner. The well shall be killed with water or mud and pump pressure applied. Should the pressure gauge on the casinghead reflect the applied pressure, the casing shall be condemned. After corrective measures have been taken, the casing shall be tested in the same manner. This method shall be used when the origin of the pressure cannot be determined otherwise.]~~

~~[(6) Christmas tree. All completed wells shall be equipped with Christmas tree fittings and wellhead connections with a rated working pressure equal to, or greater than, the surface shut-in pressure of the well. The tubing shall be equipped with a master valve, but two master valves shall be used on all wells with surface pressures in excess of 5,000 psi. All wellhead connections shall be assembled and tested prior to installation by a fluid pressure equal to the test pressure of the fitting employed.]~~

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

~~[(7) Storm choke and safety valve. A storm choke or similar safety device shall be installed in the tubing of all completed flowing wells to a minimum of 100 feet below the mud line. Such wells shall have the tubing-casing annulus sealed below the mud line. A safety valve shall be installed at the wellhead downstream of the wing valve. All oil, gas, and geothermal resource gathering lines shall have check valves at their connections to the wellhead.]~~

~~[(8) Pipeline shut-off valve. All gathering pipelines designed to transport oil, gas, condensate, or other oil or geothermal resource field fluids from a well or platform shall be equipped with automatically controlled shut-off valves at critical points in the pipeline system. Other safety equipment must be in full working order as a safeguard against spillage from pipeline ruptures.]~~

~~[(9) Training. Effective January 1, 1981, all tool pushers, drilling superintendents, and operators' representatives (when the operator is in control of the drilling) shall be required to furnish certification of satisfactory completion of a USGS-approved school on well control equipment and techniques. The certification shall be renewed every two years by attending a USGS-approved refresher course. These training requirements apply to all drilling operations on lands which underlie fresh or marine waters in Texas.]~~

(d) Exceptions or alternate programs. The director may administratively grant an exception or approve an alternate casing/tubing program required by this section provided that the

TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)

alternate casing/tubing program will achieve the intent of the rule as described in subsection (a)(1)

of this section and the following requirements are met:

(1) The request for an exception or alternate casing/tubing program shall be accompanied by the fee required by §3.78(b)(5) of this title (relating to Fees and Financial Security Requirements).

(2) An administrative exception for tubing shall not exceed a period of 180 days. A request for an exception for tubing beyond 180 days shall require a Commission order.

§3.99. Cathodic Protection Wells.

(a) Definitions. The following words and terms, when used in this section, shall have the following meanings, unless the context clearly indicates otherwise.

(1) - (2) (No change.)

(3) Protection depth--Depth or depths at which usable quality water must be protected or isolated, as determined by the Groundwater Advisory Unit of the Oil and Gas Division, which may include zones that contain brackish or saltwater if such zones are correlative and/or hydrologically connected to zones that contain usable-quality water.

(4) (No change.)

**TxOGA Suggested Revisions
RRC Proposed Amendments SWR 13 (1.25.13 DRAFT)**

(b) - (h) (No change.)

§3.100. Seismic Holes and Core Holes.

(a) Definitions. The following words and terms, when used in this section, shall have the following meanings, unless the context clearly indicates otherwise.

(1) - (3) (No change.)

(4) Protection depth--Depth or depths at which usable quality water must be protected or isolated, as determined by the Groundwater Advisory Unit of the Oil and Gas Division, which may include zones that contain brackish or saltwater if such zones are correlative and/or hydrologically connected to zones that contain usable-quality water.

(5) - (6) (No change.)

(b) - (f) (No change.)